

Axis Group Of Interior Design

To,

Date: 16/01/2019

DR. SR BANERJEE

Project No- Ax-SrJD-14012019P757

Garden Tower - 2 , Uniworld City , Newtown

Pin - 700135, West Bengal India

SUMMARY		
Sl. No.	Particulars	Amount (Rs)
1	Interior works (Project type- LHD LHM) (LUXURY HIGH DESIGN & LUXURY HIGH MATERIAL)	Grand Total = 4769550 /-
	GRAND TOTAL INCLUDING (13%) DISCOUNT	Grand Total = 4769550 /-

Note:-

- 1.Extra charges will be applicable for extra work.
- 2.Payment condition:- 35% Advance to be paid along with the work order, another 35% after 40% progress of work, further 25% after 70% progress of work and rest 5% after final completion of job and handover of the site.
- 3.The total time period for completion of job is 150 days

FOR AROID (Mohsin Ali (Director))	CLIENT SIGNATURE (FINAL APPROVAL)
--	-----------------------------------

Sub. : Quotation For Interior Fit out work

Sl. No.	Description	Amount	
BEDROOM 1			
1	Providing and making Wardrobe made of 19 mm th ply finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.	Project type- LHD LHM (LUXURY HIGH DESIGN & LUXURY HIGH MATERIAL) Total Area - 1574 sqft SQFT RATE- 3483/- TOTAL AMOUNT = 5482242 /- Discount Amount (13%) = 712691 /-	
2	Providing and making Bed made of PLY finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.		
3	Providing & fixing UNDER WINDOW SEATING		
4	Providing & fixing bed back wall full paneling works		
5	Providing & fixing BEDSIDE TABLE		
6	Providing & fixing Dressing unit		
7	Providing & fixing T.V Unit		
8	Providing & fixing Wall niche design		
BEDROOM 2			
1	Providing and making Wardrobe made of 19 mm th ply finished with 1 mm th lam from outside and 0.8 mm th laminate from inside.	Grand Total = 4769550 /-	
2	Providing and making bed made of PLY finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.		
3	Providing and making side table cum mirror unit made of 19 mm th ply finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.		
4	Providing & fixing T.V UNIT		
5	Providing and making 2 seater sofa		
6	Providing & fixing bed back wall Paneling		
MASTER BEDROOM			
1	Providing and making Bed made of PLY finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.		
2	Providing and making side table made of 19 mm th ply finished with 1 mm th lam from outside and 0.8 mm th laminate from inside.		
3	Providing and making Dressing unit made of 19 mm th ply finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.		
4	Providing and making 2 seater I shape sofa made of 19 mm th ply finished with 1 mm th lam. from outside and 0.8 mm th laminate from inside.		
5	Providing and making G. Wardrobe made of 19 mm th ply finished with 1 mm th lam from outside and 0.8 mm th laminate from inside		
6	Providing and making F. Wardrobe made of 19 mm th ply finished with 1 mm th lam from outside and 0.8 mm th laminate from inside		
7	Providing and fixing working table		
8	Providing and making Display cum book shelves unit		
9	Providing & fixing t.v unit		
10	Providing & fixing center table		
LIVING & DINING AREA			
1	Providing & making of 6 Seater wooden dinning table , (glass top) made with ply and lam., including labour & material.		
2	Providing and fixing chaires		
3	Providing and fixing 5 SEATER SOFA with puff		
4	Providing and fixing Center table		
5	Providing and fixing dining table back wall brick work with wooden paneling works		
6	Providing decorative hanging lights .		
7	Providing and fixing multipurpose t.v unit		
8	Providing and fixing disply with bar unit		
9	Providing and fixing sofa back wall paneling works		
10	Providing and fixing shoe unit CUM DISPLAY		
11	Providing and fixing Crockery unit		
12	Providing and fixing Indoor plants design for 2 side balcony		
13	Providing and fixing CHARCOAL DESIGN		
14	Providing and fixing PASSAGE AREA LOFT WORKS		

Description	
PUJA CUM LOUNGE ROOM	
1	Providing and fixing PUJA UNIT
2	Providing and fixing STORAGE UNIT
3	Providing and fixing STUDY TABLE
4	Providing and fixing BOOK SHELVES
5	Providing and fixing SOFA CUM BED
6	Providing and fixing SOFA CUM BED BACK WALL PANELING
7	Providing and fixing Center table
Description	
KITCHEN	
1	Down/Base cabinet : Providing and fixing Down/Base cabinet under existing counter slab, made of plywood, finish with 1mm Laminate on out side & 0.8mm laminate on inside (as per sample approve) with all required hardware.
2	Over head/Top cabinet : Providing and fixing Overhead/Top cabinet, made of plywood, finish with 1mm laminate on out side & 0.8mm laminate on inside with all required hardware.
3	Accessories:
4	i) S.S Basket a.ss utensil basket Nos.1, b.ss cutlery basket. Nos.- 1, c.ss cup&saucer. Nos- 1, d.ssb pullout Nos.- 1, e.ss cylinder trolley Nos.- 1, f.Ss bin holder Nos.- 1,
5	ii) S.S Sink
6	Wall Tiles:
7	Granite Counter:(As per Choice of Material)
Miscellaneous Work	
1	Main door design with veneer finish and hardware.
2	Electrical works
3	Providing & Fixing Doors design
4	Providing & Fixing POP designer false ceiling works.
5	Providing & Fixing wooden designer false ceiling works
6	Providing & Fixing window Paneling
7	Providing & Fixing Paint & Putty works
8	Providing & Fixing wall paper
9	Providing & Fixing texture paint
10	Providing & Fixing ALL BATHROOM FITTINGS CHANGES WORKS
11	Providing & Fixing FLOOR TILES WORKS
12	Providing & Fixing BATHROOMS WALL & FLOOR TILES WORKS
13	Dismantling works
TOTAL PAYBLE AMOUNT	
Grand Total = 4769550 /-	

In addition , we also give Warranty of materials & products regarding the category.

Luxury: Premium quality Design, Top grade Materials, imported showpiece products as well as higher budget.

- + 5 years free service warranty from our company,**
- + 25 years plywood warranty from our company.**
- + Others material warranty as per the material company.**

*** Warranty will be applicable if and only if company's fault has been found. Company will not be responsible if any fault occurs from client side.**

***Quotations will be prepared with the Codes of category.**

*** For more details, visit our website — www.agointeriordesign.com/company-portfolio**

[DESIGN] [MATERIAL] [RATE]	LHD Luxury High Design 33 sqft	LMD Luxury Medium Design 29 sqft	LBD Luxury Basic Design 25 sqft	SHD Standard High Design 21 sqft	SMD Standard Medium Design 19 sqft	SBD Standard Basic Design 17 sqft	BHD Basic High Design 13 sqft
LHM Luxury High Materials 3450 sqft	LHD LHM 3483 sqft	LMD LHM 3479 sqft	LBD LHM 3475 sqft	SHD LHM 3471 sqft	SMD LHM 3469 sqft	SBD LHM 3467 sqft	BHD LHM 3463 sqft
LMM Luxury Medium Materials 3000 sqft	LHD LMM 3033 sqft	LMD LMM 3029 sqft	LBD LMM 3025 sqft	SHD LMM 3021 sqft	SMD LMM 3019 sqft	SBD LMM 3017 sqft	BHD LMM 3013 sqft
LBM Luxury Basic Materials 2700 sqft	LHD LBM 2733 sqft	LMD LBM 2729 sqft	LBD LBM 2725 sqft	SHD LBM 2721 sqft	SMD LBM 2719 sqft	SBD LBM 2717 sqft	BHD LBM 2713 sqft
SHM Standard High Materials 2450 sqft	LHD SHM 2483 sqft	LMD SHM 2429 sqft	LBD SHM 2475 sqft	SHD SHM 2471 sqft	SMD SHM 2469 sqft	SBD SHM 2467 sqft	BHD SHM 2463 sqft
SMM Standard Medium Materials 2250 sqft	LHD SMM 2283 sqft	LMD SMM 2279 sqft	LBD SMM 2275 sqft	SHD SMM 2271 sqft	SMD SMM 2269 sqft	SBD SMM 2267 sqft	BHD SMM 2263 sqft
SBM Standard Basic Materials 2100 sqft	LHD SBM 2133 sqft	LMD SBM 2129 sqft	LBD SBM 2125 sqft	SHD SBM 2121 sqft	SMD SBM 2119sqft	SBD SBM 2117 sqft	BHD SBM 2113 sqft
BHM Basic High Materials 1700 sqft	LHD BHM 1733 sqft	LMD BHM 1729 sqft	LBD BHM 1725 sqft	SHD BHM 1721 sqft	SMD BHM 1719 sqft	SBD BHM 1717 sqft	BHD BHM 1713 sqft